



B727

Normal Procedures Checklist

FAA Approved

01 AUG 26

Before Starting Engines

Pilots

PARKING BRAKE SET
OXYGEN & MASKS CHECKED ‡
WINDOW & PROBE HEAT ON
PRESSURIZATION SET
FLIGHT & STANDBY INSTRUMENTS.. CHECKED
WARNING SYSTEMS CHECKED
ALTIMETERS & CLOCKS SET ‡
RADIOS SET ‡
TRIMS ZERO / ZERO
BRAKE PRESSURES CHECKED
GEAR LEVER & LIGHTS DOWN and GREEN ‡
ENGINE START LEVERS CUTOFF
RADAR & TRANSPONDER STANDBY
ANTI-SKID & ANTI-ICE OFF
EMERGENCY EXIT LIGHTS ARMED
FLT ATTENDANT & T.O. BRIEF COMPLETED

Engineer

BATTERY ON
FUEL QUANTITY &
DISTRIBUTION ___ LBS and CHECKED ‡
BOOST PUMPS ONE ON EACH TANK
CROSSFEED VALVES NO. 2 OPEN

Above 172 000 LBS . . . ALL OPEN

B PUMPS ONE ON
HYD & ENGINE OIL QTY CHECKED
BLEED VALVES OPEN
ELECTRICAL PANEL & DC POWER CHECKED
FIRE CONTROL & OVERHEAT WARN. CHECKED
AIR CONDITIONING and BLEEDS SET
A PUMPS & RUDDER POWER ON



‡ Challenge and response item

Before Starting Engines (cont)

Ten Minutes Prior to Departure

FASTEN BELTS ON
LOGBOOK and FLIGHT FORMS CHECKED ‡

Prior to Engine Start or Pushback

FUEL & HYDRAULIC PANELS SET
DOORS / WINDOWS CLOSED / LOCKED ‡
ANTI-COLLISION LIGHTS ON
CABIN READY REPORT RECEIVED
FLIGHTDECK DOOR CLOSED and SECURED

When Clear to Start Engine(s)

PACKS OFF

After Start

Pilots

ENGINE START LEVERS IDLE DETENT
ENGINE ANTI-ICE AS REQUIRED

Engineer

ELEC POWER, PUMPS & HYD CHECKED
DOOR WARNING LIGHTS OUT

Delayed Engine Start

Pilots

ENGINE START LEVERS IDLE DETENT
ENGINE ANTI-ICE AS REQUIRED

Engineer

ELEC POWER & HYD PRESSURE CHECKED
GALLEY POWER & BOOST PUMPS ON
HYD BRAKE INTERCONNECT CLOSED
AIR CONDITIONING and BLEEDS SET

Before Taxi / Taxi

After All Engines Start

Pilots

FLAPS & RUNWAY ____, GREEN LIGHT ‡
TO DATA & BUGS CHECKED ‡
STAB TRIM ____, UNITS ‡
FLIGHT CONTROLS &
YAW DAMPERS CHECKED
SEAT BELTS & HARNESS ON

Engineer

AIR CONDITIONING and BLEEDS SET
GALLEY POWER & FUEL HEAT CHECKED
AUTO PACK TRIP AS REQUIRED



Before Takeoff

Pilots

ICING CONSIDERATIONS CHECKED
IGNITION & ANTI-SKID ON
TRANSPONDER TA / RA

Engineer

APU LIGHT OUT
BOOST PUMPS, X-FEED & OIL CLR CHECKED

When Approaching Number One Position

CABIN ALERT COMPLETED

Just Prior To Takeoff Roll

LIGHTS ON

After Takeoff – Climb

Pilots

FLAPS UP / NO LIGHTS
GEAR LEVER OFF
IGNITION ON
ANTI-ICE AS REQUIRED
LANDING & LOGO LIGHTS OFF

Engineer

AIR CONDITIONING and BLEEDS SET
PRESSURIZATION & HYD PUMPS CHECKED
AUTO PACK TRIP CUTOUT

Descent

Pilots

PRESSURIZATION CHECKED
ANTI-ICE AS REQUIRED
LANDING DATA PREPARED
LDG DATA & BUGS CHECKED ‡
APPROACH BRIEFING COMPLETE

Approaching Transition Level

ALTIMETERS XX.XX and CROSSCHECKED ‡



10,000 Ft AFL

EXTERIOR LIGHTS AS REQUIRED
FASTEN BELTS ON

Engineer

SEAT BELTS & HARNESS ON
FUEL PANEL, CABIN ALT & CBs CHECKED
HYDRAULIC PUMPS ON



Before Landing

Pilots

SEAT BELTS ON
BRAKE PRESSURE CHECKED
IGNITION ON
SPOILERS ARMED, GREEN LIGHT ‡
GEAR DOWN and GREEN ‡
FLAPS _____, GREEN LIGHT ‡

Engineer

ANTI-SKID CHECKED
INTL: ALTIMETERS inHg / mb

After Landing – Taxi

When Clear of Landing Runway

Pilots

SPOILERS DOWN
FLAPS UP
ANTI-SKID & IGNITION OFF
RADAR, XPDR & DME STANDBY
STAB TRIM ZERO

Engineer

BLEED VALVES & GALLEY POWER CHECKED

About One Minute Prior to Gate Arrival

APU AS REQUIRED

Parking

Pilots

PARKING BRAKE SET
ENGINE START LEVERS CUTOFF
PASSENGER SIGNS, ANTI-ICE & HEAT OFF
ANTI-COLLISION LIGHTS & RADAR OFF
TRANSPONDER STBY
LOG BOOK COMPLETED

Engineer

BOOST PUMPS OFF
B PUMPS & O2 / OIL / HYD QTYS CHECKED

On Overnight Terminations

EMER EXIT LTS, GALLEY & RADIOS OFF
BATTERY OFF